DirecTV Schedule of Installation Fees and Services

Standard Receiver Professional Installation Includes:

- Mounting and grounding the DirecTV dish to within 20 feet of utility ground on an exterior wall of a single family dwelling and within a 100 foot cable length of the connected television.
- Installing up to 100 feet of exterior RG-6 cable to one (1) DirecTV (primary) receiver through one collocated exterior and interior wall to include inductance loop.
- Routing of cable through a standard wood frame structure or a single layer of masonry.
- Connection of the primary DirecTV receiver.
- Connecting primary DirecTV receiver to a phone jack, if receiver is within 25 feet of phone jack.
- Maximize the signal strength of the DirecTV programming.
- Consumer education on the basic operation of the DirecTV receiver.
- Contact Programmer(s) to activate account(s).
- Obtain signed Programmer(s) contract, Sign Off of completed installation work order, and Sales Terms by the consumer.

Standard Receiver Professional Installation Does Not Include:

- Install or relocation of additional receivers (unless purchased separately).
- Extra RG-6 cable over 100 feet per run.
- Mounting and grounding the DirecTV system 18" mini-dish on any surface of the home where a 25 foot ladder cannot reach.
- Drilling through more than 1 collocated exterior and interior wall.
- Phone jack wiring where existing service is more than 25 feet from receiver.
- Providing any enhancements to existing phone or audio/visual systems.
- Connections to stereo, VCRs, and/or various audio components that are not collocated with the DirecTV receiver.
- Special moldings or other cosmetic hardware used to hide exposed cables.
- Non-penetrating roof mount, pole mount, or chimney mount.
- Removal and/or repair of previously mounted equipment.

Multi-Room Standard Receiver Professional Installation Includes:

- Includes all of the items listed above for Standard Receiver Professional Installation plus...
- Installing and routing up to 100 feet of RG-6 cable per DirecTV (secondary) receiver(s) through one collocated exterior and interior wall.
- Connection of the additional secondary DirecTV receiver(s).
- Connecting additional secondary DirecTV receiver(s) to a phone jack, if receiver(s) is/are within 25 feet of a phone jack.
- Consumer education on the basic operation of the secondary DirecTV receiver(s) (if applicable).

Advanced (2-tuner) Receiver Professional Installation Includes:

- Includes all of the items listed above for Standard Receiver Professional Installation plus...
- Provide installation and routing of one (1) additional line of up to 100 feet of RG-6 coaxial cable to run from one (1) additional LNB port to one (1) advanced (2-tuner) receiver through the same collocated exterior and interior entry points.
- Customer is responsible for downloading additional services once DirecTV programming has been activated.

Regulations:

- 1) National Electric code recommends all dish installations be grounded within 20 feet to the house Utility Ground.
- 2) FCC Part 68.213c requires inside phone wiring to meet minimum standards of category 3.

DBS Satellite Residential Flat Service Fee Schedule

Pole Mount.		
a) Installation where pole and cable previously existed. (\$20)		
b) Installations where pole is available, cable is not usable (\$3.50 per		
foot of trenching.)		
c) Installations where pole & cable are not available. (\$40 plus \$3.50		
per foot of trenching.)		
* This line item does not include digging hole through rock or		
obstructions. Installation not to exceed 1 hour.		
Cable trench per foot	\$3.50	
Fish cable through single wall	\$50	
Attic Cable Run, coax cost \$2.50/foot	\$30-80	
Drilling through walls, per wall, after first wall	\$15	
Ground Rod	\$30	
Basement Runs, coax cost \$2.50/foot	\$25-50	
Installing Telephone Cable Connections per hour	\$20	
External RG6 coax per foot in excess of 100 feet not to exceed 150 total	\$3.50	
Crawl Space Cable Run, coax cost \$2.50/foot	\$45-75	
Ceiling Tile Run, coax cost \$2.50/foot	\$30-90	
Ground Wire run over 20 feet, per foot	\$1.00	
General Construction billable cost per hour	\$17	
Low Voltage Electrical billable cost per hour	\$20	
Certified Data Technician billable cost per hour	\$40	
Certified Electrican's billable cost per hour	\$30	

Explanation of any additional charges: